Official Notice No. 165-2011 Howard Purification Plant HP-180: OZONE BUILDING WALL STABILIZATION AND REPAIR November 29, 2011

ADDENDUM NO. 1

This Addendum consists of the following **CHANGES TO THE BID DOCUMENTS FOR OFFICIAL NOTICE 165-2011**:

1. PLEASE SEE THE RESPONSES BELOW TO THE REQUEST FOR INFORMATION SUBMITTED:

HP-180 RFI RESPONSES (O.N. 165-2011)

1. Could the engineer give us an idea of the length of the damaged joint to be repaired as shown on Detail #5 on Contract Drawing HP-180-03? We observed that the joint appeared to be failed along the entire length of the wall of this building. AS NOTED ON PLAN HP-180-03 THE ESTIMATED LENGTH OF DAMAGE IS 10'-0". BASED ON THE UPWARD ANGLE OF THE DAMAGED CORBEL, THE DAMAGE IS BELIEVED TO TERMINATE APPROXIMATELY 10'-0" FROM THE BUILDING'S END. PLEASE USE THE 10'-0" DIMENSION IN DETERMINING YOUR BID.