NOTES :

- (I), (II), (III), DENOTES RAMP TYPE.
- CONSTRUCT ALL CARRIAGE WALKS AND DRIVEWAYS PER CITY OF MILWAUKEE SPECIFICATIONS.
- OFFSET MEASUREMENTS TO TREES, WOOD POLES AND LIGHT POLES ARE TAKEN TO EDGE NEAREST THE CENTERLINE.
- OFFSET MEASUREMENTS TO HYDRANTS ARE TAKEN TO THE OPERATING NUT.
- GRADE & PLACE 1.5' WIDTH OF SOD IN LAWN AREAS DISTURBED BY CONSTRUCTION, UNLESS OTHERWISE DIRECTED.

CONDITION OF CONCRETE

- BROKEN
- BLUE LINED
- BACK PITCHED
- CRACKED
- EXCESSIVE PITCH
- HEAVED
- JOINT FAILURE
- MUD JACKED
- PATCHED
- POOR CONDITION
- SETTLED
- SPALLED
- VERY GOOD
- VERY POOR

ESTIMATE / CERTIFICATE QUANTITIES

	DESCRIPTION	UNIT	ASSESS.	X-ING			PLAN TOT.	PROJ. TOT.
X	MOBILIZATION	L.S.						
	FINISHING ROADWAY	L.S.						
X	BARRICADING AND SIGNING	L.S.						
X	CUTTING	C.Y.						
	ROADWAY CUTTING	C.Y.						
X	FILLING	C.Y.						
	ROADWAY FILLING	C.Y.						
	PAVEMENT REMOVAL	S.Y.						
	BITUMINOUS SURFACE REMOVAL	S.Y.						
X	CURB &/OR CURB & GUTTER REMOVAL	L.F.						
X	CONC. WALK &/OR DRIVEWAY REMOVAL	S.F.						
X	SAWING (FULL DEPTH)	L.F.						
X	SAWING	L.F.						
	TREES CLEARING	I.D.						
	TREES GRUBBING	I.D.						
X	31" CONCRETE CURB & GUTTER	L.F.						
	V.T. CONC. WALK &/OR DRIVEWAY	C.Y.						
X	5" CONCRETE WALK	S.F.						
	7" CONCRETE DRIVEWAY	S.F.						
	CONCRETE PAVEMENT	S.Y.						
	7" CONCRETE ALLEY PAVEMENT	S.Y.						
X	V.T. CONCRETE BASE	C.Y.						
	CONCRETE BASE	S.Y.						
	TACK COAT	GAL.						
	BASE PREP. FOR ASPHALT SURFACE	L.S.						
	V.T. ASPH. CONC. PAV'T. (MAX.)	S.Y.						
X	3" ASPHALT BIKE PATH	S.Y.						
X	6" CRUSHED STONE BASE	S.Y.						
	CRUSHED GRAVEL BASE							
X	GRAVEL FILLING	TON						
X	SODDING	S.Y.						
X	TOPSOIL	C.Y.						
	PAVEMENT GRINDING (ASPHALT)	S.Y.						
	PAVEMENT GRINDING (CONCRETE)	S.Y.						
	SEALING PAV'T JOINTS & CRACKS	S.Y.						
	MANHOLE RINGS	EACH						
	SEWER FRAME ADJUSTMENT	V.F.						
	MANHOLE SEAL (CITY FURNISHED)	EACH						
X	EROSION CONTROL (TYPE M)	EACH						

DEPARTMENT OF PUBLIC WORKS
INFRASTRUCTURE SERVICES DIVISION
FIELD OPERATIONS
FIELD & DESIGN ENGINEERING
MILWAUKEE, WISCONSIN

FILE NO. 70

PLAN OF: W. ROSEDALE AVE. (300W, 2800S)

MID-BLOCK X-ING INSTALL

THIS SECTION: 500' WEST OF S. CHASE AVE.

DRAWN BY	S. BIEGANSKI	DATE: 6/13/14	PROJECT NO. ST211140155
DESCRIPTIONS BY	S. BIEGANSKI	DATE: 6/13/14	SHEET 1 OF 1
LEVELS BY	L. BEKELE	DATE: 6/4/14	SCALE 1" = 10' / 1/4 SEC. 498, 506 / ALD. DIST. 14
LEVELS TRANSF. BY	M. SHIBILSKI	DATE: 6/5/14	
DESIGNED BY	R. DUCHOW	DATE: 6/9/14	OBSTRUCTIONS - SEE OBSTRUCTION LIST
GRADES TRANSF. BY	S. BIEGANSKI	DATE: 6/13/14	REVISED:
CHECKED BY	D. [signature]	DATE: 6/18/14	REVISED:
APPROVED BY	[signature]	DATE: 6/18/14	REVISED:
FILE: V:\PWELIB\PAVING\29434.FIN			
PLOT DATE: 18-JUN-2014			

EROSION	CONTROL	AND	C.B.	REQUISITION	PLAN
TYPE M	X - CBW		- RESET	X - ABANDON	NO WORK
2	0		0	0	

W. ROSEDALE AVE. - MID-BLOCK X-ING INSTALL 500' W. OF S. CHASE ST.

12" X 72" ST211140155

(1 OF 1) # 29434