



Department of Public Works
Infrastructure Services Division

Ghassan Korban
Commissioner of Public Works

Preston Cole
Director of Operations

Jeffrey S. Polenske
City Engineer

September 9, 2013

Official Notice No. 69-1

Addendum No. 2

This addendum No. 2 will add the following location to the locations listed in the bid package:

North Jefferson St. from the south side of East Wells St. to the north side of East Clybourn St

No work will take place in the intersections of N. Jefferson St. and E. Mason St, N. Jefferson St. and E. Wisconsin Ave, and N. Jefferson St. and E. Michigan St.

Milling and asphalt operations for North Jefferson St. must occur in the following manner:

- A. Grind entire roadway one-half (1/2) at a time
- B. Contractor will be required to maintain one (1) 11-foot lane of traffic in each direction at all times. The maintained traffic lane must be on the existing surface or the new asphalt surface. Traffic operations will not be allowed on the milled surface except for intersections. All joints must be heated to proper temperature to prevent for formation of cold joints. All work on N. Jefferson St. must be completed in four (4) workdays.
- C. Access to parking structures and surface parking lots must be maintained at all times.
- D. Asphalt tack to be used on N. Jefferson St. is to be a no-track tack. The cost of the no-track tack will be included in the bid item of Tack Coat.

This Addendum No. 2 will change the bid quantities and will be added to the project breakdown pages.

Please acknowledge Addendum No. 2 in the proper section of the bid.

Very truly yours,

Samir Amin
Chief Construction Engineer



This addendum No. 2 will change the bid quantities and will be added to the project breakdown pages.

Please acknowledge Addendum No. 2 in the proper section of the bid.

Very truly yours.

Mazen Amer

Construction Supervisor

OFFICIAL NOTICE NO. 2013-69-1

For Construction of VT Asphalt Pavement, Grinding, etc...

(ST216130103)

High Impact Streets - asphalt resurface by contract - var. loc.

th Aldermanic District

ALL BIDS MUST BE TYPED OR PRINTED

30500	MOBILIZATION	1 Lump Sum
(Bid in figures)	\$ _____	Lump Sum
(Bid in words)	\$ _____	Lump Sum
30501	FINISHING ROADWAY	1 Lump Sum
(Bid in figures)	\$ _____	Lump Sum
(Bid in words)	\$ _____	Lump Sum
30606	BARRICADING AND SIGNING	1 Lump Sum
(Bid in figures)	\$ _____	Lump Sum
(Bid in words)	\$ _____	Lump Sum
60103	TACK COAT	1,910.00 gallon
(Bid in figures)	\$ _____	per gallon
(Bid in words)	\$ _____	per gallon
60130	VARIABLE THICKNESS ASPHALT CONCRETE PAVEMENT (1/2 INCH MAXIMUM)	3,646.00 ton
(Bid in figures)	\$ _____	per ton
(Bid in words)	\$ _____	per ton
83200	PAVEMENT GRINDING	23,884.00 sq. yd.
(Bid in figures)	\$ _____	per sq. yd.
(Bid in words)	\$ _____	per sq. yd.

OFFICIAL NOTICE NO. 2013-69-1

83306	PAVEMENT MARKING, 4" WHITE, COLD PLASTIC FURNISH AND INSTALL	3,176.00 lin. ft.
(Bid in figures)	\$ _____	per lin. ft.
(Bid in words)	\$ _____	per lin. ft.
83311	PAVEMENT MARKING, 4" YELLOW, COLD PLASTIC FURNISH AND INSTALL	5,450.00 lin. ft.
(Bid in figures)	\$ _____	per lin. ft.
(Bid in words)	\$ _____	per lin. ft.
83324	PAVEMENT MARKING, CROSSWALK 12" WHITE, COLD PLASTIC, FURNISH AND INSTALL	1,090.00 lin. ft.
(Bid in figures)	\$ _____	per lin. ft.
(Bid in words)	\$ _____	per lin. ft.
83331	PAVEMENT MARKING, CROSSWALK 24" WHITE, COLD PLASTIC, FURNISH AND INSTALL	495.00 lin. ft.
(Bid in figures)	\$ _____	per lin. ft.
(Bid in words)	\$ _____	per lin. ft.
83336	PAVEMENT MARKING, ARROWS, COLD PLASTIC, FURNISH AND INSTALL	7.00 each
(Bid in figures)	\$ _____	per each
(Bid in words)	\$ _____	per each
83341	PAVEMENT MARKING, WORDS, COLD PLASTIC, FURNISH AND INSTALL	3.00 each
(Bid in figures)	\$ _____	per each
(Bid in words)	\$ _____	per each
83570	PAVEMENT REINFORCEMENT SYSTEM (MESH)	3,765.00 sq. yd.
(Bid in figures)	\$ _____	per sq. yd.
(Bid in words)	\$ _____	per sq. yd.
97900	EROSION CONTROL	1 Lump Sum
(Bid in figures)	\$ _____	Lump Sum
(Bid in words)	\$ _____	Lump Sum

OFFICIAL NOTICE NO. 2013-69-1

TOTAL ESTIMATE:

(Bid in figures) \$ _____

(Bid in words) \$ _____

**PROJECT BREAKDOWN
OFFICIAL NOTICE # 69-1**

09/06/2013
03:31:42 PM

PROJECT TITLES

PROJECT 216-0103

PROJECT/GRANT ST216130103

ESTIMATE 29378

High Impact Streets - asphalt resurface by contract - var. loc.

**PROJECT BREAKDOWN
OFFICIAL NOTICE # 69-1**

09/06/2013
03:31:42 PM
Page 2 of 3

Project Number	216-0103	TOTAL
Plans Per Project	29378	
Roadway Width	FT.	'
Approximate Length	FT.	'

ITEM #	ITEM DESCRIPTION	UNIT		
30500	Mobilization	Lump Sum	*	1
30501	Finishing Roadway	Lump Sum	*	1
30606	Barricading and Signing	Lump Sum	*	1
60103	Tack Coat	gallons	1910	1910
60130	Variable Thickness Asphalt Concrete Pavement (1/2	tons	3646	3646
83200	Pavement Grinding	sq. yd.	23884	23884
83306	Pavement Marking, 4" White, Cold Plastic Furnish and	lin. ft.	3176	3176
83311	Pavement Marking, 4" Yellow, Cold Plastic Furnish and	lin. ft.	5450	5450
83324	Pavement Marking, Crosswalk 12" White, Cold Plastic,	lin. ft.	1090	1090
83331	Pavement Marking, Crosswalk 24" White, Cold Plastic,	lin. ft.	495	495
83336	Pavement Marking, Arrows, Cold plastic, Furnish and	each	7	7
83341	Pavement Marking, Words, Cold Plastic, Furnish and	each	3	3
83570	Pavement Reinforcement System (Mesh)	sq. yd.	3765	3765
97900	Erosion Control	Lump Sum	*	1

* Combined under one lump sum.