NOTES :

- (I), (II), (III), DENOTES RAMP TYPE.
- CONSTRUCT ALL CARRIAGE WALKS AND DRIVEWAYS PER CITY OF MILWAUKEE SPECIFICATIONS.
- OFFSET MEASUREMENTS TO TREES, WOOD POLES AND LIGHT POLES ARE TAKEN TO EDGE NEAREST THE CENTERLINE.
- OFFSET MEASUREMENTS TO HYDRANTS ARE TAKEN TO THE OPERATING NUT.
- GRADE & PLACE 1.5' WIDTH OF SOD IN LAWN AREAS DISTURBED BY CONSTRUCTION UNLESS OTHERWISE DIRECTED.
- SLOPE FROM FLOW LINE TO EDGE OF ALLEY VARIES. (SCREED REQUIRED)

W. STEVENSON ST. / N. 75TH ST. / N. 74TH ST. / W. DIXON ST.

CONDITION OF CONCRETE
B BROKEN
BL BLUE LINED
BP BACK PITCHED
C CRACKED
EP EXCESSIVE PITCH
H HEAVED
JF JOINT FAILURE
MJ MUD JACKED
P PATCHED
PC POOR CONDITION
S SETTLED
SP SPALLED
VGC VERY GOOD
VPC VERY POOR

ESTIMATE / CERTIFICATE QUANTITIES

	DESCRIPTION	UNIT	ASSESS.	X-ING			PLAN TOT.	PROJ.TOT.
X	MOBILIZATION	L.S.						
X	FINISHING ROADWAY	L.S.						
X	BARRICADING AND SIGNING	L.S.						
X	CUTTING	C.Y.						
X	ROADWAY CUTTING	C.Y.						
X	FILLING	C.Y.						
X	ROADWAY FILLING	C.Y.						
X	PAVEMENT REMOVAL	S.Y.						
	BITUMINOUS SURFACE REMOVAL	S.Y.						
	CURB &/OR CURB & GUTTER REMOVAL	L.F.						
X	CONC.WALK &/OR DRIVEWAY REMOVAL	S.F.						
X	SAWING (FULL DEPTH)	L.F.						
	SAWING	L.F.						
	TREES CLEARING	I.D.						
	TREES GRUBBING	I.D.						
	CONCRETE CURB & GUTTER	L.F.						
	V.T. CONC.WALK &/OR DRIVEWAY	C.Y.						
	5" CONCRETE WALK	S.F.						
	7" CONCRETE DRIVEWAY	S.F.						
	CONCRETE PAVEMENT	S.Y.						
X	7" CONCRETE ALLEY PAVEMENT	S.Y.						
X	V.T. CONCRETE BASE	C.Y.						
	CONCRETE BASE	S.Y.						
	TACK COAT	GAL.						
	BASE PREP. FOR ASPHALT SURFACE	L.S.						
X	V.T.ASPH.CONC.PAV'T.(MAX.)	TONS						
X	4" CRUSHED STONE BASE	S.Y.						
	CRUSHED GRAVEL BASE							
X	GRAVEL FILLING	TON						
X	SODDING	S.Y.						
X	TOPSOIL	C.Y.						
	PAVEMENT GRINDING (ASPHALT)	S.Y.						
	PAVEMENT GRINDING (CONCRETE)	S.Y.						
X	SEALING PAV'T JOINTS & CRACKS	S.Y.						
	MANHOLE RINGS	EACH						
X	SEWER FRAME ADJUSTMENT	V.F.						
	MANHOLE SEAL (CITY FURNISHED)	EACH						
X	EROSION CONTROL (TYPE M)	EACH						

DEPARTMENT OF PUBLIC WORKS INFRASTRUCTURE SERVICES DIVISION FIELD OPERATIONS FIELD & DESIGN ENGINEERING MILWAUKEE, WISCONSIN			FILE NO. 230
PLAN OF: ALLEY BETW. W DIXON ST., W STEVENSON, (100s, 7400w) N 74TH ST, N 75TH ST (S'LY(N-S)&(E-W))			
THIS SECTION:			
DRAWN BY G GUERRA	DATE: 01/30/14	PROJECT NO. ST212140131	SHEET 1 OF 1
DESCRIPTIONS BY G GUERRA	DATE: 01/30/14		
LEVELS BY W.WILLIAMS	DATE: 11/23/13	SCALE 1" = 10'	1/4 SEC. 406-419 / ALD.DIST. 10
LEVELS TRANSF. BY	DATE:		
DESIGNED BY M.SCHULTZ	DATE: 2/11/14	OBSTRUCTIONS - SEE OBSTRUCTION LIST	
GRADES TRANSF. BY D.BEKELE	DATE: 2/13/14	REVISED:	
CHECKED BY D. Ulrbach	DATE: 3/5/14	REVISED:	
APPROVED BY	DATE: 3/15/14	REVISED:	
FILE: V:\PWELIB\PAVING\29393.FIN			
PLOT DATE: 28-FEB-2014			

STORM DRAINAGE UNITS		
C.B.W. - 0	RESET - 1	ABANDON - 0
PROJECT IN (SEPARATED) AREA		

DATE / TO	3/10/14	6/26/14
ESTIMATING	1	
HOLLOW WALKS		
PUBLIC HEARING	1	
CONSTRUCTION	1	6
SEWER	1	
WATER	1	
STREET LIGHTING	1	
BLDG. SEWERS	1	
MEASURING		1
FIELD		
DISTRICT FILE	1	2
FORESTRY	1	
W.E. / G.O.	1	
WIS. GAS CO.	1	
TRANSIT SYSTEM		
CABLE TV		
UND. GRD. COND.	1	
WATER DIST.	1	
WEPCO N/S	1	
WEPCO S/S		
SEWER SERVICES		
UTILITY COOR.	1	
TrafficEng RM 506	1	6
PLAN SIZE	12" X 11"	

W. STEVENSON AVE. / N. 75TH ST. / N. 74TH ST. / W. DIXON ST.

EROSION CONTROL	AND C.B.	REQUISITION	PLAN
TYPE M: 0	☒ - CBW: 0	☐ - RESET: 1	X - ABANDON: 0	NO WORK

ALLEY BETW. W DIXON & W STEVENSON, N 74TH ST, N 75TH ST (S'LY(N-S)&(E-W)) (1 OF 1) # 29393 ST212140131 "12" X 11"