



Samir Amin, P.E.
Transportation Infrastructure
Engineer in Charge

Department of Public Works
Infrastructure Services Division
Field Operations – Construction Section

September 7, 2016

OFFICIAL NOTICE NO. 96-1-2016

Addendum No. 1

NOTICE TO CONTRACTORS intending to bid on the above noted Official Notice, which appeared in the Daily Reporter on August 31, 2016, with a Bid Opening Date on September 14, 2016 at 10:30 A.M.

This addendum is issued to notify those who are interested in bidding on this project that the attached **Project Breakdown sheets (2-sheets)**, for Official Notice No. 96-1-2016, shall be added to the 2016 Bid Package for this project..

The bidder shall acknowledge receipt of this addendum on the acknowledgement page (paper bid)/section (Bid Express).

Very truly yours,

William Frasc
Chief Construction Engineer

c: Lynn Des Jardins

Attachments

**PROJECT BREAKDOWN
OFFICIAL NOTICE # 96-1**

08/24/2016
10:04:46 AM

PROJECT TITLES

PROJECT 814-0136

PROJECT/GRANT ST211140136

ESTIMATE 29350

N. 39th St. - W. Locust St. to W. Chambers St.

**PROJECT BREAKDOWN
OFFICIAL NOTICE # 96-1**

08/24/2016
10:04:46 AM
Page 2 of 3

Project Number		814-0136	TOTAL
Plans Per Project		29350	
Roadway Width	FT.	1	
Approximate Length	FT.	26'	
		720'	

ITEM #	ITEM DESCRIPTION	UNIT		
30500	Mobilization	Lump Sum	*	1
30501	Finishing Roadway	Lump Sum	*	1
30606	Barricading and Signing	Lump Sum	*	1
40121	Cutting	cu. yd.	40	40
40122	Roadway Cutting	cu. yd.	413	413
40131	Filling	cu. yd.	36	36
40211	Pavement Removal	sq. yd.	122	122
40231	Curb and/or Curb and Gutter Removal	lin. ft.	1397	1397
40241	Concrete Walk and/or Driveway Removal	sq. ft.	9700	9700
40261	Sawing (Full Depth)	lin. ft.	47	47
40262	Sawing	lin. ft.	30	30
40411	Trees Clearing	in. dia.	36	36
40412	Trees Grubbing	in. dia.	36	36
50200	Concrete Curb and Gutter	lin. ft.	1400	1400
50315	5 inch Concrete Walk	sq. ft.	8745	8745
50330	Detectable Warning Field	sq. ft.	128	128
50570	7 inch Concrete Pavement	sq. yd.	1469	1469
50580	8 inch Concrete Pavement	sq. yd.	97	97
70203	3 inch Crushed Gravel Base	sq. yd.	97	97
70500	Gravel Filling	tons	75	75
82200	Sodding	sq. yd.	1378	1378
82300	Topsoil	cu. yd.	77	77
83400	Sealing Pavement Joints and Cracks	sq. yd.	1566	1566
83800	Drill and Install Reinforcing Rods	each	107	107
84320	Water Valve Box Adjustment	each	8	8
84325	Water Service Box Adjustment	each	30	30
84511	Manhole / Inlet Adjustment Type I	each	7	7
97003	Abandon Storm Water Inlet or Catch Basin	each	2	2
97180	Inlet Frame and Cover Type 57	each	2	2
97181	Manhole Frame and Cover Type 58A	each	2	2
97213	Inlet, Type 45A	each	2	2
97220	Manhole/Inlet Repair	vert. ft.	1	1
97328	8" PVC Pipe	lin. ft.	63	63
97900	Erosion Control	Lump Sum	*	1
99741	CUC Manhole Adjustment Type I	each	1	1

* Combined under one lump sum.